



ADDENDUM NO. 1

March 19th-2024

Re: Cache Bay Outdoor Rink Replacement

The following Addendum shall be part of the RFQ Document and shall supersede the bid specification sheets in RFQ package.

INDICATE RECEIPT OF THIS ADDENDUM ON THE TENDER FORM.

This Addendum consists of 2 pages.

Section 3 (General Condition)

16.3) Temporary Service and Facilities:

The changeroom facility will be made available as a temporary facility and the contractor will be responsible to leave the facility in the same condition as when the contractor started the project.

Section 4 (Special Provision)

RINK BOARDS

Execution

Add the following sentence

9. Contractor to add one 2x4x4' backing at inside corners and middle wall end panels where intersecting the perimeter boards of Option B. Contractor shall use two 3-1/2 hot galvanized ardox spiral nails at 12" on center to secure panels.



Section 4 (Special Provision)

GATES

Execution item 1.

Delete sentence

“Construction of new gates to be as per section 5.1,5.2 and 5.3 and drawings,”

And replace with

“Construction of new gates to be as per drawings option A and B Detail F and specifications,”

Section 4 (Special Provision)

ELECTRICAL

Product

Delete sentence

“Wooden pressure treated hydro poles to match existing poles dimensions and to be ESA approved.

And replace with

“Wooden pressure treated poles to be minimum Class 3 poles.

Execution

Add the following sentence

New hydro poles shall be buried 6’ deep and have a total length of 40’.